

AD A092037

DDC FILE COPY

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO. AD-A092037	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report Browns Reservoir Dam Long Island Basin, Westchester County, New York Inventory No. 763		5. TYPE OF REPORT & PERIOD COVERED Phase I Inspection Report National Dam Safety Program
7. AUTHOR(s) George Koch		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS New York Department of Environmental Conservation 50 Wolf Road Albany, NY 12233		8. CONTRACT OR GRANT NUMBER(s) ✓ DACW-51-79-C-0001
11. CONTROLLING OFFICE NAME AND ADDRESS New York State Department of Environmental Conservation 50 Wolf Road Albany, NY 12233		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of the Army 26 Federal Plaza New York District, Coff New York, NY 10287		12. REPORT DATE 30 September 1980
		13. NUMBER OF PAGES
		15. SECURITY CLASS (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; Distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES "Original contains color plates: All DTIC reproductions will be in black and white" THIS DOCUMENT IS HIGH QUALITY REPRODUCIBLE THE QUALITY OF THE REPRODUCTION IS A FUNCTION OF THE QUALITY OF THE ORIGINAL SIGNED: [Signature]		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability Broons Reservoir Dam Westchester County Silver Mine River		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization. The examination of documents and the visual inspection of Browns Reservoir Dam did not reveal conditions which constitute an immediate hazard to human life or property. However, the dam has some deficiencies which require further investigation and remedial action.		

DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

80 11 21 067

Using the Corps of Engineers "Screening Criteria" for the initial review of spillway adequacy, it has been determined that the embankment would be overtopped for all storms in excess of 38% of the PMF (Probable Maximum Flood). The spillway is, therefore, adjudged as "seriously inadequate", and the dam is assessed as unsafe, non-emergency.

The classification of "unsafe" applied to a dam because of a "seriously inadequate" spillway is not meant to connote the same degree of emergency as would be associated with an "unsafe" classification applied for a structural deficiency. It does mean that there appears to be a serious deficiency in the spillway capacity and if a severe storm were to occur, overtopping and failure of the dam could take place, significantly increasing the hazard to loss of life downstream of the dam.

It is, therefore, recommended that within 3 months of notification to the owner, detailed hydrologic/hydraulic investigations of the structure be undertaken to more accurately determine the site specific characteristics of the watershed and their affect upon the overtopping potential of the dam. The results of these investigations will determine the appropriate remedial measures which will be required to achieve a spillway capacity adequate to discharge the outflow from at least the 1/2 PMF. The investigations should be completed within 1 year and remedial measures completed during the following year. In the interim, a detailed emergency action plan must be developed and implemented during periods of unusually heavy precipitation. Also, around-the-clock surveillance of the structure must be provided during these periods.

In addition the dam has a number of problem areas, which if left uncorrected, have the potential for the development of potentially hazardous conditions, and must be corrected within 1 year. These areas are:


1. Monitor the seepage at the toe of slope below the outlet works, at bi-weekly intervals with the aid of weirs. Also monitor the soft wet area below the right spillway buttress.
2. Repair the deteriorated concrete of the spillway and spillway buttresses.
3. Remove the vegetation observed on the embankments and along the downstream channels. Provide a program of periodic cutting and mowing of these surfaces.
4. Repair the minor erosion observed on the downstream slopes of the embankments near the spillway buttresses.
5. Investigate the condition of the wet well and the valves within the gate house. Repair as required to return these valves to operational status. The valves in the gate house should be used for control instead of those in the outlet chamber to reduce the internal pressures within the pipe and embankment.
6. Provide a program of periodic inspection and maintenance of the dam and appurtenances, including yearly operation and lubrication of all valves. Document this information for future reference. The emergency action plan described in section 7.1d should be maintained and updated periodically during the life of the structure.

LONG ISLAND BASIN
BROWNS RESERVOIR DAM

WESTCHESTER COUNTY NEW YORK

INVENTORY NO. N.Y. 763

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM



NEW YORK DISTRICT CORPS OF ENGINEERS

JULY, 1980

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED
CONTRACT NO. DACW-51-79-C0001

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

Acceptance For	<input checked="" type="checkbox"/> <input type="checkbox"/> <input type="checkbox"/>
NTIS () & DTIC TIB	
Unannounced Justification	
By	
Distribution/Availability Codes	
Avail and or Special	
Dist	A

11/30 Sep 78

12/105

⑥ PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
BROWNS RESERVOIR DAM I.D. No. 763 Inventory Number II
DEC #232 BE-4367 LONG ISLAND BASIN, NY-3
WESTCHESTER COUNTY, NEW YORK

Number

Phase I Inspection Report

TABLE OF CONTENTS

⑩ George/K...

PAGE NO.

- ASSESSMENT	-
- OVERVIEW PHOTOGRAPH	-
1 PROJECT INFORMATION	1
1.1 GENERAL	1
1.2 DESCRIPTION OF PROJECT	1
1.3 PERTINENT DATA	2
2 ENGINEERING DATA	4
2.1 GEOLOGY	4
2.2 SUBSURFACE INVESTIGATION	4
2.3 DAM AND APPURTENANT STRUCTURES	4
2.4 CONSTRUCTION RECORDS	5
2.5 OPERATION RECORDS	5
2.6 EVALUATION OF DATA	5
3 VISUAL INSPECTION	6
3.1 FINDINGS	6
3.2 EVALUATION	7
4 OPERATION AND MAINTENANCE PROCEDURES	9
4.1 PROCEDURES	9
4.2 MAINTENANCE OF THE DAM	9
4.3 WARNING SYSTEM	9
4.4 EVALUATION	9

393970

mt

	<u>PAGE NO.</u>
5 HYDRAULIC/HYDROLOGIC	10
5.1 DRAINAGE AREA CHARACTERISTICS	10
5.2 ANALYSIS CRITERIA	10
5.3 SPILLWAY CAPACITY	10
5.4 RESERVOIR CAPACITY	10
5.5 FLOODS OF RECORD	10
5.6 OVERTOPPING POTENTIAL	10
5.7 EVALUATION	10
6 STRUCTURAL STABILITY	11
6.1 EVALUATION OF STRUCTURAL STABILITY	11
6.2 STABILITY ANALYSIS	11
7 ASSESSMENT/RECOMMENDATIONS	13
7.1 ASSESSMENT	13
7.2 RECOMMENDED MEASURES	13

APPENDIX

- A. PHOTOGRAPHS
- B. VISUAL INSPECTION CHECKLIST
- C. HYDROLOGIC/HYDRAULIC DATA AND COMPUTATIONS
- D. REFERENCES
- E. STRUCTURAL STABILITY
- F. DRAWINGS

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam	Browns Reservoir (I.D. No. NY 763)
State Located	New York
County Located	Westchester
Stream	Silver Mine River
Date of Inspection	July 9, 1980

ASSESSMENT

The examination of documents and the visual inspection of Browns Reservoir Dam did not reveal conditions which constitute an immediate hazard to human life or property. However, the dam has some deficiencies which require further investigation and remedial action.

Using the Corps of Engineers "Screening Criteria" for the initial review of spillway adequacy, it has been determined that the embankment would be overtopped for all storms in excess of 38% of the PMF (Probable Maximum Flood). The spillway is, therefore, adjudged as "seriously inadequate", and the dam is assessed as unsafe, non-emergency.

The classification of "unsafe" applied to a dam because of a "seriously inadequate" spillway is not meant to connote the same degree of emergency as would be associated with an "unsafe" classification applied for a structural deficiency. It does mean that there appears to be a serious deficiency in the spillway capacity and if a severe storm were to occur, overtopping and failure of the dam could take place, significantly increasing the hazard to loss of life downstream of the dam.

It is, therefore, recommended that within 3 months of notification to the owner, detailed hydrologic/hydraulic investigations of the structure be undertaken to more accurately determine the site specific characteristics of the watershed and their affect upon the overtopping potential of the dam. The results of these investigations will determine the appropriate remedial measures which will be required to achieve a spillway capacity adequate to discharge the outflow from at least the 1/2 PMF. The investigations should be completed within 1 year and remedial measures completed during the following year. In the interim, a detailed emergency action plan must be developed and implemented during periods of unusually heavy precipitation. Also, around-the-clock surveillance of the structure must be provided during these periods.

In addition the dam has a number of problem areas, which if left uncorrected, have the potential for the development of potentially hazardous conditions, and must be corrected within 1 year. These areas are:

1. Monitor the seepage at the toe of slope below the outlet works, at bi-weekly intervals with the aid of weirs. Also monitor the soft wet area below the right spillway buttress.
2. Repair the deteriorated concrete of the spillway and spillway buttresses.
3. Remove the vegetation observed on the embankments and along the downstream channels. Provide a program of periodic cutting and mowing of these surfaces.
4. Repair the minor erosion observed on the downstream slopes of the embankments near the spillway buttresses.
5. Investigate the condition of the wet well and the valves within the gate house. Repair as required to return these valves to operational status. The valves in the gate house should be used for control instead of those in the outlet chamber to reduce the internal pressures within the pipe and embankment.
6. Provide a program of periodic inspection and maintenance of the dam and appurtenances, including yearly operation and lubrication of all valves. Document this information for future reference. The emergency action plan described in section 7.1d should be maintained and updated periodically during the life of the structure.

George Koch

George Koch
Chief, Dam Safety Section
New York State Department
of Environmental Conservation
NY License No. 45937

Approved By:

W. M. Smith Jr.
Colonel W. M. Smith Jr.
New York District Engineer

Date:

30-Sep-88




Photo #1 Overview of Brown's Reservoir Dam

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
BROWNS RESERVOIR DAM I.D. No. 763
DEC #232 BE-4361 LONG ISLAND BASIN
WESTCHESTER COUNTY, NEW YORK

SECTION 1: PROJECT INFORMATION

1.1 GENERAL

a. Authority

The Phase I inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367.

b. Purpose of Inspection

Evaluation of the existing conditions of the subject dam to identify deficiencies and hazardous conditions, determine if they constitute hazards to human life and property and recommend measures where necessary.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam and Appurtenances

Browns Reservoir Dam consists of a 175.5 feet long stepped concrete spillway constructed between 2 homogeneous earth embankments (left embankment length=200 feet, right embankment length=1000 feet), the maximum height of which is 48 feet. The upstream slopes of the earth embankments are 1 vertical on 2 horizontal, the downstream slopes are 1 on 1.5, and the crest of the dam is 14 feet wide. A concrete and cyclopean core wall, located along the centerline of the embankments, extends from 1.5 feet below the crest to a variable depth. Plans indicate that the core wall is 2 feet wide at the top and slopes outward at a rate of 3/4 inches per foot on both the upstream and downstream faces. A gate house and gate chamber located near the right abutment of the right embankment contains three gate valves which control the flow through a 6 inch, 16 inch and 30 inch pipe. The 6 inch pipe provides drainage within the well. The 16 and 30 inch pipes provide discharge from the reservoir to augment the capacity of the 2 downstream reservoirs, which supply water to the City of Norwalk, Connecticut. An outlet chamber at the downstream toe of the embankment also contains valves for the 16 and 30 inch pipes. These valves are currently used to control the downstream discharge.

b. Location

The dam is located on the Silver Mine River, approximately 6 miles north of the City of Norwalk, Connecticut.

c. Size

The dam is 48 feet high and impounds approximately 890 acre-feet. The dam is classified as "intermediate" in size (40 to 100 feet in height).

d. Hazard Classification

The dam is classified as "high" hazard due to the potential for a chain reaction failure situation of the dams within the Silver Mine River Basin which are above the City of Norwalk.

e. Ownership

The dam is owned and operated by the City of Norwalk, First Water District, Mr. William Leahy, Superintendent of Filter Plant & Watershed, 3 Beldon Avenue, Norwalk, Connecticut. Telephone: (203)966-1473.

f. Purpose of the Dam

The dam provides storage for the supply of water to the City of Norwalk, Connecticut.

g. Design and Construction

The dam was designed by Charles M. Wood, and was built in 1910 by the Jabson Hacker Co., New York, N.Y. The dam was raised in 1924 from elevation 414 to its present height at elevation 420, by Frank B. Hastings, contractor, the engineer was Samuel W. Hoyt Jr. Company Inc. All available information concerning the construction and reconstruction has been included in Appendix F. The dam is composed of a concrete spillway constructed between two earth embankments, the maximum height of which is 48 feet.

h. Normal Operating Procedures

All flows in excess of the demand for water by the City of Norwalk are discharged over the spillway.

1.3 PERTINENT DATA

a. <u>Drainage Area</u> (sq. mi.)	7.56
b. <u>Discharge at Dam</u> (cfs)	
Spillway at Maximum High Water	3931
Reservoir Drain at Normal Water Elevation	190
c. <u>Elevations</u> (USGS Datum)	
Top of Dam	436.
Spillway Crest	432.
Reservoir Drain Invert	390.
d. <u>Reservoir</u> (acres)	
Surface Area at Top of Dam	55.
Surface Area at Crest of Dam	44.
e. <u>Storage Capacity</u> (acre feet)	
Top of Dam	1067
Spillway Crest	891
f. <u>Dam</u>	
Type: Homogeneous Earth with cyclopean concrete core wall.	
Length (ft):	1200.
Slopes upstream	2:1
downstream	1 1/2:1
Crest Width (ft):	14'

g. Spillway

Type: Stepped concrete overflow structure.

Weir Length (ft):

175.5'

h. Reservoir Drain

Type: Two concrete encased pipes 16 & 30 inches.

Control: Manual control valves at the gate and toe of the dam.

SECTION 2: ENGINEERING DATA

2.1 GEOLOGY

Browns Reservoir Dam is located in the "New England Uplands" physiographic province of New York State. Maximum relief is in the Hudson Highlands, where elevations range from 800 feet below sea level (bedrock of the Hudson River Valley) to more than 1500 feet. Rocks in these uplands are either metamorphic or igneous, and land forms are closely related to their durability. Strong topographic linearity characterizes the Hudson Highlands; most of the ridges and valleys follow the northeast-southwest strike of the metamorphosed rocks.

The "Landforms and Bedrock Geology of New York State" prepared by the University of the State of New York indicates that the bedrock in the vicinity of the dam is the Hartland Formation - basal amphibolite overlain by pelitic schists. (Middle Ordovician through lower Cambrian rocks initially deformed by the Taconic Orogeny (435-455 million years ago) and subsequently by the Acadian Orogeny.) The "Generalized Tectonic-Metamorphic Map of New York", compiled by Fisher, Isachsen, and Richard (1971) indicates that the tectonic unit in the vicinity of the dam is "eugeosynclinal (rise-rock)" thrust sheets, intensely deformed with carbonate slivers along faults.

The "Preliminary Brittle Structures Map of New York" developed by Isachsen and McKendree (1977), does not indicate the presence of any faulting or other brittle deformations within the vicinity of the dam or impoundment. Several topographic linear features are present to the north and west, but are a significant distance from the dam.

2.2 SUBSURFACE INVESTIGATION

No subsurface investigation could be located for the dam. The "General Soil Map of New York State" prepared by Cornell University Agriculture Experiment Station, indicates that the surficial soils are Charlton Soils of glacial till origin. These soils are formed on unstratified variable glacial till and residuum predominantly from schists but in places including gneiss and granite. The soils are stony silt and sand with a trace of clay. In places ledge pieces and boulders are numerous. Rock outcrops are common, but the depth to rock is extremely variable. The overall drainage and permeability is good. The soil is also considered erodible due to the limited clay content.

2.3 DAM AND APPURTENANT STRUCTURES

The dam was built in 1910 by the Jabson Hooker Co., New York, N.Y.; the engineer was Charles M. Wood. The dam was raised in 1924 to its present height by the contractor Frank B. Hastings; the engineer was Samuel W. Hoyt Jr. Company, Inc. All available information concerning the construction and reconstruction has been included in Appendix F. The dam is composed of a concrete spillway and two earth embankments the maximum height of which is 48 feet.

2.4 CONSTRUCTION RECORDS

No construction records were located for the dam.

2.5 OPERATION RECORDS

All operation records are on file with the owner.

2.6 EVALUATION OF DATA

The data presented in this report has been, in part, compiled from information obtained from Mr. Robert Mercurio and Mr. Harry Everson of the City of Norwalk, Connecticut. This information appears adequate and reliable for Phase I inspection purposes.

SECTION 3: VISUAL INSPECTION

3.1 FINDINGS

a. General

Visual inspection of Browns Reservoir Dam was conducted on July 9, 1980. The weather was clear and the temperature ranged in the upper 60's. The water surface at the time of the inspection was just cresting the spillway.

b. Spillway

The concrete spillway located near the left abutment of the dam is stepped to dissipate the energy of the overflow. The construction joints are deteriorated and require repair. Spillway flow masked careful examination of the downstream face. No significant seepage was observed and no seepage was reported by the maintenance staff. (See Photo #1) The approach channel is riprapped and appears to be in good condition. A few stones have been displaced. (See Photo #2) Gravel and stone was noted at the base of the spillway. This area is in good condition. The top surfaces of the spillway buttresses are deteriorated (particularly the left buttress) and require repairs. (See Photos #1 & 2). The horizontal and vertical alignment of the spillway appears to be good.

c. Embankment

The embankment is divided into 2 sections by the spillway. The left embankment is in generally good condition. (See Photo #2) Some vegetation was observed on the upstream face near the water line (See Photo #4), and some slight erosion is present near the crest of the embankment left of the left spillway buttress (See Photo #3).

The right embankment is in good condition with the following exceptions:

1. Extensive tree and brush growth on the downstream slope. Some of the trees have been removed by maintenance forces in the vicinity of the spillway, and it was reported that this program would be instituted along the remainder of the embankment. (See Photos #4 & 5)
2. In the vicinity of the spillway approximately 50 feet beyond the toe of the embankment a soft wet area is present, with water seeking vegetation. Mowing equipment has rutted the surface and water is laying in this area. This area may be the result of the backwater at the base of the spillway. (See Photo #3) No evidence of active seepage was observed. Evidence of erosion of the downstream slope about 20 feet from the right spillway buttress was noted. (See Photo #6)
3. In the area adjacent to the downstream toe and slightly to the left of the gate house, seepage was evident at a rate of 5 to 10 gpm. (See Photo #10) The seepage appeared to be originating from an area downstream of the embankment, and was flowing toward the embankment and then turning to the right and flowing toward the outlet works for the gatehouse. No evidence of particle migration was noted.

4. On the left side of the concrete outlet structure, 5 separate and distinct areas were observed in which seepage was flowing toward the outlet structure. (See Photos #8 & 9) Some minor sediment was noted at several locations where the seepage was discharging into the backwater adjacent to the outlet structure. The flows appeared to be clear and no active particle migration was observed. Some of the flow appears to be originating from an elevated area of natural origin, left of the outlet structure. One of the flows originates on the right side near the embankment, flows parallel to the toe and emerges on the left side of the outlet structure. This seepage is being ponded by the irregular grade near the toe, and has a rusty appearance, but the flow is clear. The total quantity of seepage from all areas is estimated to be 20 to 30 gpm. It is possible that some of the flow is related to rains of the previous day. The maintenance staff reports that this seepage has been present for at least 6 years.

While the slopes of the right embankment appears to be steep, no evidence of sliding, sloughing, depressions, or seepage was observed on the slopes, along the crest or at the abutments.

d. Outlet Works

The 1909 plans indicate that the outlet works, located near the right abutment of the right earth embankment, consists of a masonry and concrete gatehouse atop a concrete gate chamber. Three gate valves controls, for a 6", 16", and 30" pipe, were observed in the gate house at the crest of the embankment. (See Photo #7) The outlet chamber (referred to as the "outlet parapet wall" in the 1909 plans) at the downstream toe of the embankment contains two valves (for 16 and 30 inch pipes). (See Photo #8) No valve was observed for the 6" pipe, which appears to be a drain for removal of water within the gate chamber. Maintenance forces were unaware of the existence of the valves within the gate chamber, indicating that these valves had not been operated for some time. Control of the outflow is provided by the downstream valves in the outlet chamber, which indicates that the upstream valves are open at least partially. All valves should be investigated and returned to operational status.

e. Downstream Channels

The downstream channel below the outlet chamber is heavily vegetated. (See Photo #9) The downstream channel below the spillway is also vegetated heavily. This vegetation should be removed to prevent blockage of the outflow.

f. Reservoir

There are no visible signs of instability or sedimentation problems within the reservoir area.

3.2 EVALUATION

The problem areas observed during the inspection and the recommended remedial actions are as follows:

1. The seepage observed along the toe of the dam requires monitoring at bi-weekly intervals with aid of weirs.

2. The soft wet area below the right spillway buttress requires monitoring.
3. The construction joints of the spillway and the spillway buttresses are deteriorated and require repair.
4. Extensive tree and brush growth was observed on the right embankment, the upstream slope of the left embankment and the downstream channels. This vegetation should be cut as soon as possible and a program of periodic cutting and mowing of these surfaces instituted.
5. Minor erosion was observed on the downstream slopes of the embankments near the spillway buttresses. Regrade and seed as required to restore these slopes to their original configuration.
6. Investigate the condition of all valves. Restore these valves, to operational status. Operate the 6 inch drain so that the water within the wet wall is removed and inspect the wall and appurtenances thoroughly. Initiate repairs as required. Use of the upstream valves for control of releases will reduce the internal pressure within the pipes.
7. Provide a program of periodic inspection and maintenance of the dam and appurtenances including yearly operation and lubrication of all valves. Document this information for future reference. Also develop an emergency action plan.

SECTION 4: OPERATION AND MAINTENANCE PROCEDURES

4.1 PROCEDURES

The normal water surface elevation is approximated by the crest of the spillway. Water can be released to the downstream channel by the outlet works via the 16 and 30 inch diameter pipes which are currently controlled by the valves in the outlet chamber. By using the valves in the gate house, instead of those in the outlet chamber, excess pressure within the pipe and the embankment will be eliminated. The invert elevation of these pipes within the gate house is 372. A 6 inch diameter pipe and valve located within the gate house may be used to drain the gate house wet wall.

4.2 MAINTENANCE OF THE DAM

Maintenance of the dam is not considered adequate as evidenced by the deterioration of the spillway, extensive vegetation on the embankment and the unoperated valves within the gate house.

4.3 WARNING SYSTEM

There is no warning system in effect or in preparation.

4.4 EVALUATION

The dam and appurtenances have not been maintained in satisfactory condition as noted in "Section 3: Visual Inspection."

SECTION 5: HYDRAULIC/HYDROLOGIC

5.1 DRAINAGE AREA CHARACTERISTICS

Delineation of the watershed of Browns Reservoir was made using the USGS quadrangles for Peach Lake, Pound Ridge, New York and Bethel, Norwalk North Connecticut. The basin consists of woodlands and fields with many residences in the lower portion. Relief is moderate, with some upland storage in the form of swampy areas and small ponds. The total area is 7.56 square miles.

5.2 ANALYSIS CRITERIA

The analysis of the spillway capacity of the dam and storage of the reservoir was performed using the Corps of Engineers HEC-1 computer model. The unit hydrograph was defined using the Snyder Synthetic Unit Hydrograph Method and the Modified Puls routing procedure was incorporated. The Probable Maximum Precipitation (PMP) used was 21.7 inches (24 hrs, 200 sq. mi) from Hydrometeorological Report No. 33. Several floods were selected (%s PMF) for analysis in accordance with recommended guidelines of the Corps of Engineers. The PMF inflow of 10,466 cfs, was routed through the reservoir and the peak outflow was determined to be 10,457 cfs.

5.3 SPILLWAY CAPACITY

A single stepped, masonry overflow spillway is located near the left abutment. It has a width of 175.5' and has a capacity of 3931. cfs at top of dam. Top of dam is 4 feet above spillway crest. There is no auxiliary or emergency spillway at Browns Reservoir.

5.4 RESERVOIR CAPACITY

Normal flood control storage capacity of the reservoir between the spillway crest and top of dam is 176. acre feet. This volume represents a total runoff of .44 inches from the basin.

5.5 FLOODS OF RECORD

Maximum flow observed in the spillway was about 1.5', resulting in an estimated flow of 860 cfs. This flow occurred during September 1975.

5.6 OVERTOPPING POTENTIAL

The maximum capacity of the spillway is 3931. cfs before overtopping would occur.

This capacity results in the ability to pass only 38% of the PMF with very little attenuation.

5.7 EVALUATION

The dam will be overtopped in all storms greater than 38% of the PMF. The spillway is, therefore, considered to be seriously inadequate.

SECTION 6: STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations

No signs of major distress were observed in connection with the earth embankment or the spillway section. However, seepage was observed at the toe of the right embankment near the gate house, and a soft wet area was noted below the right spillway buttress.

b. Design and Construction Data

No design or construction data could be located concerning the structural stability of the dam.

c. Post-Construction Changes

In 1924, the dam was raised from a crest elevation of 414 to elevation 420. (See Appendix F)

6.2 STABILITY ANALYSIS

A stability analysis was conducted for the concrete gravity spillway section. The results of the analysis are as follows:

<u>Case</u>	<u>Description of Loading Conditions</u>
1	Normal Operating conditions, reservoir at El. 416.5 (spillway crest), full uplift, no tailwater.
2	Same as Case 1, with 5.0 kips/l.f. ice load
3	Water at 1/2 PMF level (El. 420.8) uplift as in Case 1, tailwater = 4.3 feet
4	Water at PMF level (El. 421.6) uplift as in Case 1, tailwater = 5.1 feet
5	Normal conditions as in Case 1, with seismic forces: = 0.1 (seismic Zone 3)

Note: The bottom surface of the dam has been idealized to simplify the analysis. Compare the analyzed section (Appendix E) with the spillway section in Appendix F. Elevations are based on plan datum.

<u>Case</u>	<u>Factor of Safety Overturning</u>	<u>Location of Resultant from Toe</u>	<u>Factor of Safety Sliding</u>
1	3.20	8.8	3.31
2	1.73	5.4	1.41
3	2.30	8.5	1.80
4	2.19	8.4	1.67
5	2.39	7.5	2.06

Location of middle 1/3 is 5.0 to 10.0 feet from the toe.

These results indicate that the spillway portion analyzed has factors of safety in excess of that recommended by the Corps of Engineers. The spillway is, therefore, considered to have adequate factors of safety for stability.

SECTION 7: ASSESSMENT/RECOMMENDATIONS

7.1 ASSESSMENT

a. Safety

The Phase I Inspection of Browns Reservoir Dam revealed that the spillway is "seriously inadequate", based on the Corps of Engineers "screening criteria", and outflows from any storm in excess of 38% of the PMF will overtop the dam. This overtopping could cause breaching of the earth embankment and the resulting flood-wave would significantly increase the hazard to downstream residents. For these reasons the dam has been assessed as unsafe, non-emergency.

b. Adequacy of Information

The information reviewed is considered adequate for Phase I Inspection purposes.

c. Need for Additional Investigation

Since the spillway is considered to be seriously inadequate, additional hydrologic/hydraulic investigations are required to more accurately determine the site specific characteristics of the watershed. After these investigations have been completed, remedial measures must be initiated to provide spillway capacity sufficient to discharge the outflow from the 1/2 PMF event.

d. Urgency

The additional hydrologic/hydraulic investigations must be initiated within 3 months of notification to the owner. Within 1 year, remedial measures as a result of these investigations must be initiated, with completion of these measures during the following year. In the interim, develop an emergency action plan for the notification of downstream residents and the proper governmental authorities in the event of overtopping, and provide around-the-clock surveillance of the dam during periods of extreme run-off. The problem areas listed below must be corrected within 1 year of notification.

7.2 RECOMMENDED MEASURES

1. Monitor the seepage at the toe of slope below the outlet works, at bi-weekly intervals with the aid of weirs. Also monitor the soft wet area below the right spillway buttress.
2. Repair the deteriorated concrete of the spillway and spillway buttresses.
3. Remove the vegetation observed on the embankments and along the downstream channels. Provide a program of periodic cutting and mowing of these surfaces.
4. Repair the minor erosion observed on the downstream slopes of the embankments near the spillway buttresses.
5. Investigate the condition of the wet wall and the valves within the gate house. Repair the valves as required and return to operational status. The valves in the gate house should be used for control instead of those in the outlet chamber to reduce the internal pressures.

within the pipe and embankment.

6. Provide a program of periodic inspection and maintenance of the dam and appurtenances, including yearly operation and lubrication of all valves. Document this information for future reference. The emergency action plan described in section 7.1d should be maintained and updated periodically during the life of the structure.

APPENDIX A
PHOTOGRAPHS




Photo #4 Upstream Face - Left Embankment



Photo #5 Crest - Right Embankment



Photo #6 Erosion of Right Embankment
near spillway



Photo #7 Valve Control in Gate House



Photo #8 Outlet Structure
note seepage in foreground




Photo #9 Seepage at Left of Outlet Structure



Photo #10 Seepage Left of Outlet Structure

APPENDIX B
VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST

1) Basic Data

a. General

Name of Dam Brown Reservoir
Fed. I.D. # NY 763 DEC Dam No. 232 BE -4361
River Basin Long Island
Location: Town Lewistown County Westchester
Stream Name Silvermine River
Tributary of Long Island Sound
Latitude (N) 41° 12.9' Longitude (W) 73° 29.6'
Type of Dam Homogeneous earth embankment w/ concrete spillway
Hazard Category "C" High
Date(s) of Inspection July 9, 1980
Weather Conditions Clear upper 60's
Reservoir Level at Time of Inspection approx. 14 spillway crest

b. Inspection Personnel Jamie C. Vetch Robert P. McCarty

c. Persons Contacted (Including Address & Phone No.)

Robert Mercuro, Harry Everson, Maintenance Division
Newark Water District, 3 Edison Ave., Newark Conn
(203) 966-1473 - Mr. William Leach, - Supv.
Flood Plain & Wetlands

d. History:

Date Constructed 1910 Date(s) Reconstructed 1922 raise 6 ft
1924 raise 6 ft
Designer Chas. E. Jones (1910) & Wm. H. H. Co., Inc.
Constructed By Wm. H. H. Co. (1910) & Wm. H. H. Co., Inc.
Owner City of Newark Conn.

2) Embankment

a. Characteristics

- (1) Embankment Material uniform
- (2) Cutoff Type concrete & cyclopaen masonry
- (3) Impervious Core same as (2)
- (4) Internal Drainage System none
- (5) Miscellaneous _____

b. Crest

- (1) Vertical Alignment good
- (2) Horizontal Alignment good
- (3) Surface Cracks none
- (4) Miscellaneous _____

c. Upstream Slope

- (1) Slope (Estimate) (V:H) 1:2
- (2) Undesirable Growth or Debris, Animal Burrows minimal
- (3) Sloughing, Subsidence or Depressions none

(4) Slope Protection riprap

(5) Surface Cracks or Movement at Toe _____

unobservable

d. Downstream Slope

(1) Slope (Estimate - V:H) 1 : 1.5

(2) Undesirable Growth or Debris, Animal Burrows _____

lots of vegetation

(3) Sloughing, Subsidence or Depressions none evident

(4) Surface Cracks or Movement at Toe none evident

(5) Seepage seepage in area surrounding outlet chamber below right embankment from 5 separate areas flowing into low area near outlet minor seepage in outlet pool. flow clear ~ 20 to 30 gpm. Some

(6) External Drainage System (Ditches, Trenches; Blanket) none

seepage coming from high water area near below
low of area. seepage reported to be there in a hole to some

(7) Condition Around Outlet Structure _____

backwater from channel around outlet. concrete good.

(8) Seepage Beyond Toe see (5) above

e. Abutments - Embankment Contact

(1) Erosion at Contact slight erosion near spillway
on both sides requires berthing

(2) Seepage Along Contact none visible
scuff and mud began to flow in 1962
stuck in place below right spillway to rise

3) Drainage System

a. Description of System none

b. Condition of System

c. Discharge from Drainage System

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs, Piezometers, Etc.)

none

5) Reservoir

- a. Slopes good condition
- b. Sedimentation no problems reported
- c. Unusual Conditions Which Affect Dam Scallops Res upstream on west branch Silvermine R.

6) Area Downstream of Dam

- a. Downstream Hazard (No. of Homes, Highways, etc.) 2 the water supply dams + city of Newark 5 mi
- b. Seepage, Unusual Growth heavily vegetated
see seepage @ 2.05
- c. Evidence of Movement Beyond Toe of Dam none
- d. Condition of Downstream Channel vegetated slight backwater

7) Spillway(s) (Including Discharge Conveyance Channel)

- a. General Spillway added in 1974 to increase
high flow capacity
- b. Condition of Service Spillway good
upstream
downstream
when in operation
no problems
at present

c. Condition of Auxiliary Spillway _____

None

d. Condition of Discharge Conveyance Channel _____

Let vegetated access road = 100' down stream

8) Reservoir Drain/Outlet •

Type: Pipe ☒ Conduit _____ Other _____

Material: Concrete _____ Metal ☒ Other _____

Size: 6" ~~unknown~~ 16" ~~etc~~ Length ~~unknown~~

Invert Elevations: Entrance ~~unknown~~ Exit ~~unknown~~

Physical Condition (Describe): _____ Unobservable ☒

Material: _____

Joints: _____ Alignment _____

Structural Integrity: _____

Hydraulic Capability: _____

Means of Control: Gate _____ Valve ☒ Uncontrolled _____

Operation: Operable ~~unknown~~ Inoperable ~~unknown~~ Other _____

Present Condition (Describe): _____

None in use since construction of outlet.
position valves located by the house, but
not been opened for many years

9) Structural

- a. Concrete Surfaces generally good condition
see deterioration of upper surfaces
a) buttresses / spillways
- b. Structural Cracking none of significance
- c. Movement - Horizontal & Vertical Alignment (Settlement) none such
- d. Junctions with Abutments or Embankments good condition
- e. Drains - Foundation, Joint, Face none
- f. Water Passages, Conduits, Sluices adequately repaired condition
- g. Seepage or Leakage none

h. Joints - Construction, etc. _____

deterioration of joints in spillway

i. Foundation _____

unobservable

j. Abutments _____

adequate

k. Control Gates _____

deterioration operation system not
operated for years

l. Approach & Outlet Channels _____

appear adequate

some process of riprap motion

m. Energy Dissipators (Plunge Pool, etc.) _____

none

n. Intake Structures _____

misconception concrete gate house

near right abutment

good condition

2" erosion in gate house + valves in 10' & 30'

discuss ideas to supply flow maintenance the res.

o. Stability _____

appears normal

p. Miscellaneous _____

APPENDIX C
HYDROLOGIC/HYDRAULIC
ENGINEERING DATA AND COMPUTATIONS

CHECK LIST FOR DAMS
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

1

AREA-CAPACITY DATA:

	<u>Elevation</u> (ft.)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-ft.)
1) Top of Dam	<u>436</u>	<u>55</u>	<u>1067</u>
2) Design High Water (Max. Design Pool)	<u>-</u>	<u>-</u>	<u>-</u>
3) Auxiliary Spillway Crest	<u>-</u>	<u>-</u>	<u>-</u>
4) Pool Level with Flashboards	<u>-</u>	<u>-</u>	<u>-</u>
5) Service Spillway Crest	<u>432</u>	<u>44</u>	<u>891</u>

DISCHARGES

	<u>Volume</u> (cfs)
1) Average Daily	<u>12.</u>
2) Spillway @ Maximum High Water - TOP OF DAM -	<u>3931.</u>
3) Spillway @ Design High Water	<u>-</u>
4) Spillway @ Auxiliary Spillway Crest Elevation	<u>-</u>
5) Low Level Outlet	<u>190.</u>
6) Total (of all facilities) @ Maximum High Water	<u>4121.</u>
7) Maximum Known Flood	<u>860.</u>
8) At Time of Inspection	<u>5-10 cfs.</u>

CREST:

ELEVATION: 436.0Type: homogeneous with 1/2 cypress concrete CORE WALLWidth: 14' Length: 1200'Spillover left center, STEPPED CONCRETE

Location _____

SPILLWAY:

SERVICE

AUXILIARY

432.0

Elevation

STEPPED CONCRETE OVERFLOW Type175.5'

Width

Type of Control

Uncontrolled

Controlled:

Type
(Flashboards; gate)

Number

Size/Length

Invert Material

Anticipated Length
of operating service

Chute Length

24 to 14 approach Height Between Spillway Crest
& Approach Channel Invert
(Weir Flow)

HYDROMETEOROLOGICAL GAGES:

Type : NONE

Location: —

Records:

Date - —

Max. Reading - —

FLOOD WATER CONTROL SYSTEM:

Warning System: NONE

Method of Controlled Releases (mechanisms):

16" # 30" RESERVOIR DRAIN
TO FEED LOWER WATER SUPPLY RESERVOIRS

DRAINAGE AREA: 7.56 SQ. MILES

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: WOODED - SOME RESIDENTIAL
 Terrain - Relief: MODERATE SLOPE - WELL DEFINED DRAINAGE PATH
 Surface - Soil: GOOD PERMEABILITY
 Runoff Potential (existing or planned extensive alterations to existing (surface or subsurface conditions)

NONE

Potential Sedimentation problem areas (natural or man-made; present or future)

NONE APPARENT

Potential Backwater problem areas for levels at maximum storage capacity including surcharge storage:

NO

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the Reservoir perimeter:

Location: NONE
 Elevation: _____

Reservoir:

Length @ Maximum Pool 2500 Ft. (Miles)
 Length of Shoreline (@ Spillway Crest) 7000 Ft. (Miles)

 FIELD OFFICIALS REPORT
 ON SITE VISIT
 DATE: JULY 1978
 REPORT FOR THE YEAR 1979

1. ALL OFFICIALS REPORTING
 2. ALL OFFICIALS REPORTING
 3. ALL OFFICIALS REPORTING
 4. ALL OFFICIALS REPORTING
 5. ALL OFFICIALS REPORTING
 6. ALL OFFICIALS REPORTING
 7. ALL OFFICIALS REPORTING
 8. ALL OFFICIALS REPORTING
 9. ALL OFFICIALS REPORTING
 10. ALL OFFICIALS REPORTING
 11. ALL OFFICIALS REPORTING
 12. ALL OFFICIALS REPORTING
 13. ALL OFFICIALS REPORTING
 14. ALL OFFICIALS REPORTING
 15. ALL OFFICIALS REPORTING
 16. ALL OFFICIALS REPORTING
 17. ALL OFFICIALS REPORTING
 18. ALL OFFICIALS REPORTING
 19. ALL OFFICIALS REPORTING
 20. ALL OFFICIALS REPORTING
 21. ALL OFFICIALS REPORTING
 22. ALL OFFICIALS REPORTING
 23. ALL OFFICIALS REPORTING
 24. ALL OFFICIALS REPORTING
 25. ALL OFFICIALS REPORTING
 26. ALL OFFICIALS REPORTING
 27. ALL OFFICIALS REPORTING
 28. ALL OFFICIALS REPORTING
 29. ALL OFFICIALS REPORTING
 30. ALL OFFICIALS REPORTING

 NEW YORK STATE
 DEPT OF ENVIRONMENTAL CONSERVATION
 FIELD PROTECTION BUREAU

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30
1																														
2																														
3																														
4																														
5																														
6																														
7																														
8																														
9																														
10																														
11																														
12																														
13																														
14																														
15																														
16																														
17																														
18																														
19																														
20																														
21																														
22																														
23																														
24																														
25																														
26																														
27																														
28																														
29																														
30																														

RESULTS OF ANALYSIS OF STREAM NETWORK CALCULATIONS
NUMBER OF CHANNELS AT
RIVER MOUTH TO
END OF NETWORK

10/10/55

Ref: 127140.

1945

SECRET
REF ID: A67089

此乃本館所藏之書也

DATE	TIME	DAY	JCS SPECIFICATION	IFLT	IPFT	-STAT-
200	15	0	H4 C	6	0	
		5	JUPER	0	0	
			NETFC	0	0	
			TRPT	0	0	
			TRACE	0	0	

* MULTI-PLAN ANALYSES TO BE PERFORMED

ARTICLES=	0.20	0.40	0.50	0.60	0.80	1.00
PLAN=	1	2	3	4	5	6

[illegible]

SUM-AREA AVERAGE COMPUTATIONS

INFORM FROM POST:	ICOMP	IFCNC	ITAPE	JPLT	JHPT	INATE	ISTAGE	INATE
1	0	0	0	2	C	1	0	0

DATE	TIME	TAKEA	SLIP	HYDROGRAPH DATA		PATIE	ISNEW	ISARE	LOCAL
				IRSEA	TRSPC	G.			
1945-06-10	1	7.56	0.	7.56			0	0	0

RECEIVED BY THE RECORDS SECTION
JUN 12 1964
ADD

SPR	PIS	R6	PRICIP DATA
21.70	R12	123.00	R24
123.00	111.00	123.00	123.00

264 406

LEFT	STARR	LEAVE	PAYROL	WAGE	DATA	STATS	RATION	STARTL	COSTL	ALSOX	RTI-P
U	C.	G.	1.00	C.		D.	1.00	1.00	0.10	O.	(

UNIT HYDROGRAPH DATA
DATE 5.1.2 CP=0.63 NTA= C

APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SPYDER CP AND TC ARE

SIGMA=	-2.10	RECESSION DATA
	SPC=	-0.05
	KTRK=	1.00
	TC=	21.92
	WCTR=	15.58
	INTERVALS	

[illegible]

[illegible]

[illegible]

TABLE 7, LOW TOP OF DAM, BUTTER OF READING, OR LOW-LEVEL BUTTER IS NOT WITHIN RANGE OF GIVEN ELEVATIONS IF SURFACE-ELEVATION DATA
 BUTTER OF READING ASSUMED TO BE AT 390.00
 SURFACE-ELEVATION DATA - SEE RE EXTRACTED DATA ABOVE ELEVATION 422.00

STATION 10 PLAN 10, PLOT 3
 END-OF-PERIOD HYDROGRAPH ENCLOSURES

OPIFLOH									
1.	2.	3.	4.	5.	6.	7.	8.	9.	10.
6.	6.	7.	7.	7.	7.	7.	7.	7.	6.
7.	7.	7.	7.	7.	7.	7.	7.	7.	7.
7.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.	6.	6.	6.	6.	6.	6.	6.	6.	6.
6.									

STATION

|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|

522'. At the 44.50 hours

[illegible]

12.12 51
13.12 51
14.12 52
15.12 53
16.12 54
17.12 55
18.12 56
19.12 57
20.12 58
21.12 59
22.12 60
23.12 61
24.12 62
25.12 63
26.12 64
27.12 65
28.12 66
29.12 67
30.12 68
31.12 69
1.13 70
2.13 71
3.13 72
4.13 73
5.13 74
6.13 75
7.13 76
8.13 77
9.13 78
10.13 79
11.13 80
12.13 81
13.13 82
14.13 83
15.13 84
16.13 85
17.13 86
18.13 87
19.13 88
20.13 89
21.13 90
22.13 91
23.13 92
24.13 93
25.13 94
26.13 95
27.13 96
28.13 97
29.13 98
30.13 99
31.13 100
1.14 101
2.14 102
3.14 103
4.14 104
5.14 105
6.14 106
7.14 107
8.14 108
9.14 109
10.14 110
11.14 111
12.14 112
13.14 113
14.14 114
15.14 115
16.14 116
17.14 117
18.14 118
19.14 119
20.14 120
21.14 121
22.14 122
23.14 123
24.14 124
25.14 125
26.14 126
27.14 127
28.14 128
29.14 129
30.14 130
31.14 131
1.15 132
2.15 133
3.15 134
4.15 135
5.15 136
6.15 137
7.15 138
8.15 139
9.15 140
10.15 141
11.15 142
12.15 143
13.15 144
14.15 145
15.15 146
16.15 147
17.15 148
18.15 149
19.15 150
20.15 151
21.15 152
22.15 153
23.15 154
24.15 155
25.15 156
26.15 157
27.15 158
28.15 159
29.15 160
30.15 161
31.15 162
1.16 163
2.16 164
3.16 165
4.16 166
5.16 167
6.16 168
7.16 169
8.16 170
9.16 171
10.16 172
11.16 173
12.16 174
13.16 175
14.16 176
15.16 177
16.16 178
17.16 179
18.16 180
19.16 181
20.16 182
21.16 183
22.16 184
23.16 185
24.16 186
25.16 187
26.16 188
27.16 189
28.16 190
29.16 191
30.16 192
31.16 193
1.17 194
2.17 195
3.17 196
4.17 197
5.17 198
6.17 199
7.17 200
8.17 201
9.17 202
10.17 203
11.17 204
12.17 205
13.17 206
14.17 207
15.17 208
16.17 209
17.17 210
18.17 211
19.17 212
20.17 213
21.17 214
22.17 215
23.17 216
24.17 217
25.17 218
26.17 219
27.17 220
28.17 221
29.17 222
30.17 223
31.17 224
1.18 225
2.18 226
3.18 227
4.18 228
5.18 229
6.18 230
7.18 231
8.18 232
9.18 233
10.18 234
11.18 235
12.18 236
13.18 237
14.18 238
15.18 239
16.18 240
17.18 241
18.18 242
19.18 243
20.18 244
21.18 245
22.18 246
23.18 247
24.18 248
25.18 249
26.18 250
27.18 251
28.18 252
29.18 253
30.18 254
31.18 255
1.19 256
2.19 257
3.19 258
4.19 259
5.19 260
6.19 261
7.19 262
8.19 263
9.19 264
10.19 265
11.19 266
12.19 267
13.19 268
14.19 269
15.19 270
16.19 271
17.19 272
18.19 273
19.19 274
20.19 275
21.19 276
22.19 277
23.19 278
24.19 279
25.19 280
26.19 281
27.19 282
28.19 283
29.19 284
30.19 285
31.19 286
1.20 287
2.20 288
3.20 289
4.20 290
5.20 291
6.20 292
7.20 293
8.20 294
9.20 295
10.20 296
11.20 297
12.20 298
13.20 299
14.20 300
15.20 301
16.20 302
17.20 303
18.20 304
19.20 305
20.20 306
21.20 307
22.20 308
23.20 309
24.20 310
25.20 311
26.20 312
27.20 313
28.20 314
29.20 315
30.20 316
31.20 317
1.21 318
2.21 319
3.21 320
4.21 321
5.21 322
6.21 323
7.21 324
8.21 325
9.21 326
10.21 327
11.21 328
12.21 329
13.21 330
14.21 331
15.21 332
16.21 333
17.21 334
18.21 335
19.21 336
20.21 337
21.21 338
22.21 339
23.21 340
24.21 341
25.21 342
26.21 343
27.21 344
28.21 345
29.21 346
30.21 347
31.21 348
1.22 349
2.22 350
3.22 351
4.22 352
5.22 353
6.22 354
7.22 355
8.22 356
9.22 357
10.22 358
11.22 359
12.22 360
13.22 361
14.22 362
15.22 363
16.22 364
17.22 365
18.22 366
19.22 367
20.22 368
21.22 369
22.22 370
23.22 371
24.22 372
25.22 373
26.22 374
27.22 375
28.22 376
29.22 377
30.22 378
31.22 379
1.23 380
2.23 381
3.23 382
4.23 383
5.23 384
6.23 385
7.23 386
8.23 387
9.23 388
10.23 389
11.23 390
12.23 391
13.23 392
14.23 393
15.23 394
16.23 395
17.23 396
18.23 397
19.23 398
20.23 399
21.23 400
22.23 401
23.23 402
24.23 403
25.23 404
26.23 405
27.23 406
28.23 407
29.23 408
30.23 409
31.23 410
1.24 411
2.24 412
3.24 413
4.24 414
5.24 415
6.24 416
7.24 417
8.24 418
9.24 419
10.24 420
11.24 421
12.24 422
13.24 423
14.24 424
15.24 425
16.24 426
17.24 427
18.24 428
19.24 429
20.24 430
21.24 431
22.24 432
23.24 433
24.24 434
25.24 435
26.24 436
27.24 437
28.24 438
29.24 439
30.24 440
31.24 441
1.25 442
2.25 443
3.25 444
4.25 445
5.25 446
6.25 447
7.25 448
8.25 449
9.25 450
10.25 451
11.25 452
12.25 453
13.25 454
14.25 455
15.25 456
16.25 457
17.25 458
18.25 459
19.25 460
20.25 461
21.25 462
22.25 463
23.25 464
24.25 465
25.25 466
26.25 467
27.25 468
28.25 469
29.25 470
30.25 471
31.25 472
1.26 473
2.26 474
3.26 475
4.26 476
5.26 477
6.26 478
7.26 479
8.26 480
9.26 481
10.26 482
11.26 483
12.26 484
13.26 485
14.26 486
15.26 487
16.26 488
17.26 489
18.26 490
19.26 491
20.26 492
21.26 493
22.26 494
23.26 495
24.26 496
25.26 497
26.26 498
27.26 499
28.26 500
29.26 501
30.26 502
31.26 503
1.27 504
2.27 505
3.27 506
4.27 507
5.27 508
6.27 509
7.27 510
8.27 511
9.27 512
10.27 513
11.27 514
12.27 515
13.27 516
14.27 517
15.27 518
16.27 519
17.27 520
18.27 521
19.27 522
20.27 523
21.27 524
22.27 525
23.27 526
24.27 527
25.27 528
26.27 529
27.27 530
28.27 531
29.27 532
30.27 533
31.27 534
1.28 535
2.28 536
3.28 537
4.28 538
5.28 539
6.28 540
7.28 541
8.28 542
9.28 543
10.28 544
11.28 545
12.28 546
13.28 547
14.28 548
15.28 549
16.28 550
17.28 551
18.28 552
19.28 553
20.28 554
21.28 555
22.28 556
23.28 557
24.28 558
25.28 559
26.28 560
27.28 561
28.28 562
29.28 563
30.28 564
31.28 565
1.29 566
2.29 567
3.29 568
4.29 569
5.29 570
6.29 571
7.29 572
8.29 573
9.29 574
10.29 575
11.29 576
12.29 577
13.29 578
14.29 579
15.29 580
16.29 581
17.29 582
18.29 583
19.29 584
20.29 585
21.29 586
22.29 587
23.29 588
24.29 589
25.29 590
26.29 591
27.29 592
28.29 593
29.29 594
30.29 595
31.29 596
1.30 597
2.30 598
3.30 599
4.30 600
5.30 601
6.30 602
7.30 603
8.30 604
9.30 605
10.30 606
11.30 607
12.30 608
13.30 609
14.30 610
15.30 611
16.30 612
17.30 613
18.30 614
19.30 615
20.30 616
21.30 617
22.30 618
23.30 619
24.30 620
25.30 621
26.30 622
27.30 623
28.30 624
29.30 625
30.30 626
31.30 627
1.31 628
2.31 629
3.31 630
4.31 631
5.31 632
6.31 633
7.31 634
8.31 635
9.31 636
10.31 637
11.31 638
12.31 639
13.31 640
14.31 641
15.31 642
16.31 643
17.31 644
18.31 645
19.31 646
20.31 647
21.31 648
22.31 649
23.31 650
24.31 651
25.31 652
26.31 653
27.31 654
28.31 655
29.31 656
30.31 657
31.31 658
1.32 659
2.32 660
3.32 661
4.32 662
5.32 663
6.32 664
7.32 665
8.32 666
9.32 667
10.32 668
11.32 669
12.32 670
13.32 671
14.32 672
15.32 673
16.32 674
17.32 675
18.32 676
19.32 677
20.32 678
21.32 679
22.32 680
23.32 681
24.32 682
25.32 683
26.32 684
27.32 685
28.32 686
29.32 687
30.32 688
31.32 689
1.33 690
2.33 691
3.33 692
4.33 693
5.33 694
6.33 695
7.33 696
8.33 697
9.33 698
10.33 699
11.33 700
12.33 701
13.33 702
14.33 703
15.33 704
16.33 705
17.33 706
18.33 707
19.33 708
20.33 709
21.33 710
22.33 711
23.33 712
24.33 713
25.33 714
26.33 715
27.33 716
28.33 717
29.33 718
30.33 719
31.33 720
1.34 721
2.34 722
3.34 723
4.34 724
5.34 725
6.34 726
7.34 727
8.34 728
9.34 729
10.34 730
11.34 731
12.34 732
13.34 733
14.34 734
15.34 735
16.34 736
17.34 737
18.34 738
19.34 739
20.34 740
21.34 741
22.34 742
23.34 743
24.34 744
25.34 745
26.34 746
27.34 747
28.34 748
29.34 749
30.34 750
31.34 751
1.35 752
2.35 753
3.35 754
4.35 755
5.35 756
6.35 757
7.35 758
8.35 759
9.35 760
10.35 761
11.35 762
12.35 763
13.35 764
14.35 765
15.35 766
16.35 767
17.35 768
18.35 769
19.35 770
20.35 771
21.35 772
22.35 773
23.35 774
24.35 775
25.35 776
26.35 777
27.35 778
28.35 779
29.35 780
30.35 781
31.35 782
1.36 783
2.36 784
3.36 785
4.36 786
5.36 787
6.36 788
7.36 789
8.36 790
9.36 791
10.36 792
11.36 793
12.36 794
13.36 795
14.36 796
15.36 797
16.36 798
17.36 799
18.36 800
19.36 801
20.36 802
21.36 803
22.36 804
23.36 805
24.36 806
25.36 807
26.36 808
27.36 809
28.36 810
29.36 811
30.36 812
31.36 813
1.37 814
2.37 815
3.37 816
4.37 817
5.37 818
6.37 819
7.37 820
8.37 821
9.37 822
10.37 823
11.37 824
12.37 825
13.37 826
14.37 827
15.37 828
16.37 829
17.37 830
18.37 831
19.37 832
20.37 833
21.37 834
22.37 835
23.37 836
24.37 837
25.37 838
26.37 839
27.37 840
28.37 841
29.37 842
30.37 843
31.37 844
1.38 845
2.38 846
3.38 847
4.38 848
5.38 849
6.38 850
7.38 851
8.38 852
9.38 853
10.38 854
11.38 855
12.38 856
13.38 857
14.38 858
15.38 859
16.38 860
17.38 861
18.38 862
19.38 863
20.38 864
21.38 865
22.38 866
23.38 867
24.38 868
25.38 869
26.38 870
27.38 871
28.38 872
29.38 873
30.38 874
31.38 875
1.39 876
2.39 877
3.39 878
4.39 879
5.39 880
6.39 881
7.39 882
8.39 883
9.39 884
10.39 885
11.39 886
12.39 887
13.39 888
14.39 889
15.39 890
16.39 891
17.39 892
18.39 893
19.39 894
20.39 895
21.39 896
22.39 897
23.39 898
24.39 899
25.39 900
26.39 901
27.39 902
28.39 903
29.39 904
30.39 905
31.39 906
1.40 907
2.40 908
3.40 909
4.40 910
5.40 911
6.40 912
7.40 913
8.40 914
9.40 915
10.40 916
11.40 917
12.40 918
13.40 919
14.40 920
15.40 921
16.40 922
17.40 923
18.40 924
19.40 925
20.40 926
21.40 927
22.40 928
23.40 929
24.40 930
25.40 931
26.40 932
27.40 933
28.40 934
29.40 935
30.40 936
31.40 937
1.41 938
2.41 939
3.41 940
4.41 941
5.41 942
6.41 943
7.41 944
8.41 945
9.41 946
10.41 947
11.41 948
12.41 949
13.41 950
14.41 951
15.41 952
16.41 953
17.41 954
18.41 955
19.41 956
20.41 957
21.41 958
22.41 959
23.41 960
24.41 961
25.41 962
26.41 963
27.41 964
28.41 965
29.41 966
30.41 967
31.41 968
1.42 969
2.42 970
3.42 971
4.42 972
5.42 973
6.42 974
7.42 975
8.42 976
9.42 977
10.42 978
11.42 979
12.42 980
13.42 981
14.42 982
15.42 983
16.42 984
17.42 985
18.42 986
19.42 987
20.42 988
21.42 989
22.42 990
23.42 991
24.42 992
25.42 993
26.42 994
27.42 995
28.42 996
29.42 997
30.42 998
31.42 999
1.43 1000

7.0012701
8.0012701
9.0012701
10.0012701
11.0012701
12.0012701
13.0012701
14.0012701
15.0012701
16.0012701
17.0012701
18.0012701
19.0012701
20.0012701
21.0012701
22.0012701
23.0012701
24.0012701
25.0012701
26.0012701
27.0012701
28.0012701
29.0012701
30.0012701
31.0012701
32.0012701
33.0012701
34.0012701
35.0012701
36.0012701
37.0012701
38.0012701
39.0012701
40.0012701
41.0012701
42.0012701
43.0012701
44.0012701
45.0012701
46.0012701
47.0012701
48.0012701
49.0012701
50.0012701
51.0012701
52.0012701
53.0012701
54.0012701
55.0012701
56.0012701
57.0012701
58.0012701
59.0012701
60.0012701
61.0012701
62.0012701
63.0012701
64.0012701
65.0012701
66.0012701
67.0012701
68.0012701
69.0012701
70.0012701
71.0012701
72.0012701
73.0012701
74.0012701
75.0012701
76.0012701
77.0012701
78.0012701
79.0012701
80.0012701
81.0012701
82.0012701
83.0012701
84.0012701
85.0012701
86.0012701
87.0012701
88.0012701
89.0012701
90.0012701
91.0012701
92.0012701
93.0012701
94.0012701
95.0012701
96.0012701
97.0012701
98.0012701
99.0012701
100.0012701

A. 0.15 004 TOP OF DAWY SETTER ELEVATION OF LOW-LEVEL OUTLET IS NOT WITHIN RANGE OF GIVEN ELEVATIONS IN STORAGE-ELEVATION DATA
 NOTE: IF RESERVOIR ELEVATION TO BE AT 430.00
 STORAGE-ELEVATION DATA: ALL OF EXTENDED ABOVE ELEVATION: 432.00

STATISTICAL PLANING FACTOR

SALEMAN (RETRACTS)

OUTFELLOH									
2.	4.	5.	7.	8.	9.	10.	11.	12.	
12.	12.	12.	12.	12.	16.	16.	11.	12.	
13.	13.	13.	13.	13.	16.	16.	14.	13.	
14.	14.	14.	14.	14.	15.	15.	14.	14.	
15.	15.	15.	15.	15.	15.	15.	15.	15.	
16.	16.	16.	16.	16.	15.	15.	15.	15.	
17.	17.	17.	17.	17.	15.	15.	15.	15.	
18.	18.	18.	18.	18.	15.	15.	15.	15.	
19.	19.	19.	19.	19.	15.	15.	15.	15.	
20.	20.	20.	20.	20.	17.	17.	21.	21.	
21.	21.	21.	21.	21.	67.	67.	64.	64.	
22.	22.	22.	22.	22.	141.	141.	147.	147.	
23.	23.	23.	23.	23.	136.	136.	147.	147.	
24.	24.	24.	24.	24.	102.	102.	124.	124.	
25.	25.	25.	25.	25.	81.	81.	98.	98.	
26.	26.	26.	26.	26.	80.	80.	73.	73.	
27.	27.	27.	27.	27.	83.	83.	53.	53.	
28.	28.	28.	28.	28.	46.	46.	53.	53.	
29.	29.	29.	29.	29.	203.	203.	303.	303.	
30.	30.	30.	30.	30.	229.	229.	205.	205.	
31.	31.	31.	31.	31.	570.	570.	651.	651.	
32.	32.	32.	32.	32.	1371.	1371.	657.	657.	
33.	33.	33.	33.	33.	1216.	1216.	4057.	4057.	
34.	34.	34.	34.	34.	5071.	5071.	1511.	1511.	
35.	35.	35.	35.	35.	1115.	1115.	6069.	6069.	
36.	36.	36.	36.	36.	7759.	7759.	10271.	10271.	
37.	37.	37.	37.	37.	9027.	9027.	10457.	10457.	
38.	38.	38.	38.	38.	2632.	2632.	7547.	7547.	
39.	39.	39.	39.	39.	5611.	5611.	4623.	4623.	
40.	40.	40.	40.	40.	5361.	5361.	4407.	4407.	

[illegible]

1011.15

[illegible]

J.	2097.	4097.	6097.	8097.	10097.	12097.
7.25	11					
7.30	41					
7.40	31					
7.50	41					
1.00	41					
1.10	51					
1.20	91					
1.30	91					
1.40	71					
2.00	91					
2.10	91					
2.20	101					
2.30	111					
2.40	121					
2.50	141					
3.00	161					
3.10	171					
3.20	191					
3.30	201					
3.40	211					
3.50	221					
4.00	231					
4.10	241					
4.20	251					
4.30	261					
4.40	271					
4.50	281					
5.00	291					
5.10	301					
5.20	311					
5.30	321					
5.40	331					
5.50	341					
6.00	351					
6.10	361					
6.20	371					
6.30	381					
6.40	391					
6.50	401					
7.00	411					
7.10	421					
7.20	431					
7.30	441					
7.40	451					
7.50	461					
8.00	471					
8.10	481					
8.20	491					
8.30	501					
8.40	511					
8.50	521					
9.00	531					
9.10	541					
9.20	551					
9.30	561					
9.40	571					
9.50	581					
10.00	591					
10.10	601					
10.20	611					
10.30	621					
10.40	631					
10.50	641					
11.00	651					
11.10	661					
11.20	671					
11.30	681					
11.40	691					
11.50	701					
12.00	711					
12.10	721					
12.20	731					
12.30	741					
12.40	751					
12.50	761					
13.00	771					
13.10	781					
13.20	791					
13.30	801					
13.40	811					
13.50	821					
14.00	831					
14.10	841					
14.20	851					
14.30	861					
14.40	871					
14.50	881					
15.00	891					
15.10	901					
15.20	911					
15.30	921					
15.40	931					
15.50	941					

11.12 21
12.12 22
13.12 23
14.12 24
15.12 25
16.12 26
17.12 27
18.12 28
19.12 29
20.12 30
21.12 31
22.12 32
23.12 33
24.12 34
25.12 35
26.12 36
27.12 37
28.12 38
29.12 39
30.12 40
31.12 41
1.13 42
2.13 43
3.13 44
4.13 45
5.13 46
6.13 47
7.13 48
8.13 49
9.13 50
10.13 51
11.13 52
12.13 53
13.13 54
14.13 55
15.13 56
16.13 57
17.13 58
18.13 59
19.13 60
20.13 61
21.13 62
22.13 63
23.13 64
24.13 65
25.13 66
26.13 67
27.13 68
28.13 69
29.13 70
30.13 71
31.13 72
1.14 73
2.14 74
3.14 75
4.14 76
5.14 77
6.14 78
7.14 79
8.14 80
9.14 81
10.14 82
11.14 83
12.14 84
13.14 85
14.14 86
15.14 87
16.14 88
17.14 89
18.14 90
19.14 91
20.14 92
21.14 93
22.14 94
23.14 95
24.14 96
25.14 97
26.14 98
27.14 99
28.14 100
29.14 101
30.14 102
31.14 103
1.15 104
2.15 105
3.15 106
4.15 107
5.15 108
6.15 109
7.15 110
8.15 111
9.15 112
10.15 113
11.15 114
12.15 115
13.15 116
14.15 117
15.15 118
16.15 119
17.15 120
18.15 121
19.15 122
20.15 123
21.15 124
22.15 125
23.15 126
24.15 127
25.15 128
26.15 129
27.15 130
28.15 131
29.15 132
30.15 133
31.15 134
1.16 135
2.16 136
3.16 137
4.16 138
5.16 139
6.16 140
7.16 141
8.16 142
9.16 143
10.16 144
11.16 145
12.16 146
13.16 147
14.16 148
15.16 149
16.16 150
17.16 151
18.16 152
19.16 153
20.16 154
21.16 155
22.16 156
23.16 157
24.16 158
25.16 159
26.16 160
27.16 161
28.16 162
29.16 163
30.16 164
31.16 165
1.17 166
2.17 167
3.17 168
4.17 169
5.17 170
6.17 171
7.17 172
8.17 173
9.17 174
10.17 175
11.17 176
12.17 177
13.17 178
14.17 179
15.17 180
16.17 181
17.17 182
18.17 183
19.17 184
20.17 185
21.17 186
22.17 187
23.17 188
24.17 189
25.17 190
26.17 191
27.17 192
28.17 193
29.17 194
30.17 195
31.17 196
1.18 197
2.18 198
3.18 199
4.18 200
5.18 201
6.18 202
7.18 203
8.18 204
9.18 205
10.18 206
11.18 207
12.18 208
13.18 209
14.18 210
15.18 211
16.18 212
17.18 213
18.18 214
19.18 215
20.18 216
21.18 217
22.18 218
23.18 219
24.18 220
25.18 221
26.18 222
27.18 223
28.18 224
29.18 225
30.18 226
31.18 227
1.19 228
2.19 229
3.19 230
4.19 231
5.19 232
6.19 233
7.19 234
8.19 235
9.19 236
10.19 237
11.19 238
12.19 239
13.19 240
14.19 241
15.19 242
16.19 243
17.19 244
18.19 245
19.19 246
20.19 247
21.19 248
22.19 249
23.19 250
24.19 251
25.19 252
26.19 253
27.19 254
28.19 255
29.19 256
30.19 257
31.19 258
1.20 259
2.20 260
3.20 261
4.20 262
5.20 263
6.20 264
7.20 265
8.20 266
9.20 267
10.20 268
11.20 269
12.20 270
13.20 271
14.20 272
15.20 273
16.20 274
17.20 275
18.20 276
19.20 277
20.20 278
21.20 279
22.20 280
23.20 281
24.20 282
25.20 283
26.20 284
27.20 285
28.20 286
29.20 287
30.20 288
31.20 289
1.21 290
2.21 291
3.21 292
4.21 293
5.21 294
6.21 295
7.21 296
8.21 297
9.21 298
10.21 299
11.21 300
12.21 301
13.21 302
14.21 303
15.21 304
16.21 305
17.21 306
18.21 307
19.21 308
20.21 309
21.21 310
22.21 311
23.21 312
24.21 313
25.21 314
26.21 315
27.21 316
28.21 317
29.21 318
30.21 319
31.21 320
1.22 321
2.22 322
3.22 323
4.22 324
5.22 325
6.22 326
7.22 327
8.22 328
9.22 329
10.22 330
11.22 331
12.22 332
13.22 333
14.22 334
15.22 335
16.22 336
17.22 337
18.22 338
19.22 339
20.22 340
21.22 341
22.22 342
23.22 343
24.22 344
25.22 345
26.22 346
27.22 347
28.22 348
29.22 349
30.22 350
31.22 351
1.23 352
2.23 353
3.23 354
4.23 355
5.23 356
6.23 357
7.23 358
8.23 359
9.23 360
10.23 361
11.23 362
12.23 363
13.23 364
14.23 365
15.23 366
16.23 367
17.23 368
18.23 369
19.23 370
20.23 371
21.23 372
22.23 373
23.23 374
24.23 375
25.23 376
26.23 377
27.23 378
28.23 379
29.23 380
30.23 381
31.23 382
1.24 383
2.24 384
3.24 385
4.24 386
5.24 387
6.24 388
7.24 389
8.24 390
9.24 391
10.24 392
11.24 393
12.24 394
13.24 395
14.24 396
15.24 397
16.24 398
17.24 399
18.24 400
19.24 401
20.24 402
21.24 403
22.24 404
23.24 405
24.24 406
25.24 407
26.24 408
27.24 409
28.24 410
29.24 411
30.24 412
31.24 413
1.25 414
2.25 415
3.25 416
4.25 417
5.25 418
6.25 419
7.25 420
8.25 421
9.25 422
10.25 423
11.25 424
12.25 425
13.25 426
14.25 427
15.25 428
16.25 429
17.25 430
18.25 431
19.25 432
20.25 433
21.25 434
22.25 435
23.25 436
24.25 437
25.25 438
26.25 439
27.25 440
28.25 441
29.25 442
30.25 443
31.25 444
1.26 445
2.26 446
3.26 447
4.26 448
5.26 449
6.26 450
7.26 451
8.26 452
9.26 453
10.26 454
11.26 455
12.26 456
13.26 457
14.26 458
15.26 459
16.26 460
17.26 461
18.26 462
19.26 463
20.26 464
21.26 465
22.26 466
23.26 467
24.26 468
25.26 469
26.26 470
27.26 471
28.26 472
29.26 473
30.26 474
31.26 475
1.27 476
2.27 477
3.27 478
4.27 479
5.27 480
6.27 481
7.27 482
8.27 483
9.27 484
10.27 485
11.27 486
12.27 487
13.27 488
14.27 489
15.27 490
16.27 491
17.27 492
18.27 493
19.27 494
20.27 495
21.27 496
22.27 497
23.27 498
24.27 499
25.27 500
26.27 501
27.27 502
28.27 503
29.27 504
30.27 505
31.27 506
1.28 507
2.28 508
3.28 509
4.28 510
5.28 511
6.28 512
7.28 513
8.28 514
9.28 515
10.28 516
11.28 517
12.28 518
13.28 519
14.28 520
15.28 521
16.28 522
17.28 523
18.28 524
19.28 525
20.28 526
21.28 527
22.28 528
23.28 529
24.28 530
25.28 531
26.28 532
27.28 533
28.28 534
29.28 535
30.28 536
31.28 537
1.29 538
2.29 539
3.29 540
4.29 541
5.29 542
6.29 543
7.29 544
8.29 545
9.29 546
10.29 547
11.29 548
12.29 549
13.29 550
14.29 551
15.29 552
16.29 553
17.29 554
18.29 555
19.29 556
20.29 557
21.29 558
22.29 559
23.29 560
24.29 561
25.29 562
26.29 563
27.29 564
28.29 565
29.29 566
30.29 567
31.29 568
1.30 569
2.30 570
3.30 571
4.30 572
5.30 573
6.30 574
7.30 575
8.30 576
9.30 577
10.30 578
11.30 579
12.30 580
13.30 581
14.30 582
15.30 583
16.30 584
17.30 585
18.30 586
19.30 587
20.30 588
21.30 589
22.30 590
23.30 591
24.30 592
25.30 593
26.30 594
27.30 595
28.30 596
29.30 597
30.30 598
31.30 599
1.31 600
2.31 601
3.31 602
4.31 603
5.31 604
6.31 605
7.31 606
8.31 607
9.31 608
10.31 609
11.31 610
12.31 611
13.31 612
14.31 613
15.31 614
16.31 615
17.31 616
18.31 617
19.31 618
20.31 619
21.31 620
22.31 621
23.31 622
24.31 623
25.31 624
26.31 625
27.31 626
28.31 627
29.31 628
30.31 629
31.31 630
1.32 631
2.32 632
3.32 633
4.32 634
5.32 635
6.32 636
7.32 637
8.32 638
9.32 639
10.32 640
11.32 641
12.32 642
13.32 643
14.32 644
15.32 645
16.32 646
17.32 647
18.32 648
19.32 649
20.32 650
21.32 651
22.32 652
23.32 653
24.32 654
25.32 655
26.32 656
27.32 657
28.32 658
29.32 659
30.32 660
31.32 661
1.33 662
2.33 663
3.33 664
4.33 665
5.33 666
6.33 667
7.33 668
8.33 669
9.33 670
10.33 671
11.33 672
12.33 673
13.33 674
14.33 675
15.33 676
16.33 677
17.33 678
18.33 679
19.33 680
20.33 681
21.33 682
22.33 683
23.33 684
24.33 685
25.33 686
26.33 687
27.33 688
28.33 689
29.33 690
30.33 691
31.33 692
1.34 693
2.34 694
3.34 695
4.34 696
5.34 697
6.34 698
7.34 699
8.34 700
9.34 701
10.34 702
11.34 703
12.34 704
13.34 705
14.34 706
15.34 707
16.34 708
17.34 709
18.34 710
19.34 711
20.34 712
21.34 713
22.34 714
23.34 715
24.34 716
25.34 717
26.34 718
27.34 719
28.34 720
29.34 721
30.34 722
31.34 723
1.35 724
2.35 725
3.35 726
4.35 727
5.35 728
6.35 729
7.35 730
8.35 731
9.35 732
10.35 733
11.35 734
12.35 735
13.35 736
14.35 737
15.35 738
16.35 739
17.35 740
18.35 741
19.35 742
20.35 743
21.35 744
22.35 745
23.35 746
24.35 747
25.35 748
26.35 749
27.35 750
28.35 751
29.35 752
30.35 753
31.35 754
1.36 755
2.36 756
3.36 757
4.36 758
5.36 759
6.36 760
7.36 761
8.36 762
9.36 763
10.36 764
11.36 765
12.36 766
13.36 767
14.36 768
15.36 769
16.36 770
17.36 771
18.36 772
19.36 773
20.36 774
21.36 775
22.36 776
23.36 777
24.36 778
25.36 779
26.36 780
27.36 781
28.36 782
29.36 783
30.36 784
31.36 785
1.37 786
2.37 787
3.37 788
4.37 789
5.37 790
6.37 791
7.37 792
8.37 793
9.37 794
10.37 795
11.37 796
12.37 797
13.37 798
14.37 799
15.37 800
16.37 801
17.37 802
18.37 803
19.37 804
20.37 805
21.37 806
22.37 807
23.37 808
24.37 809
25.37 810
26.37 811
27.37 812
28.37 813
29.37 814
30.37 815
31.37 816
1.38 817
2.38 818
3.38 819
4.38 820
5.38 821
6.38 822
7.38 823
8.38 824
9.38 825
10.38 826
11.38 827
12.38 828
13.38 829
14.38 830
15.38 831
16.38 832
17.38 833
18.38 834
19.38 835
20.38 836
21.38 837
22.38 838
23.38 839
24.38 840
25.38 841
26.38 842
27.38 843
28.38 844
29.38 845
30.38 846
31.38 847
1.39 848
2.39 849
3.39 850
4.39 851
5.39 852
6.39 853
7.39 854
8.39 855
9.39 856
10.39 857
11.39 858
12.39 859
13.39 860
14.39 861
15.39 862
16.39 863
17.39 864
18.39 865
19.39 866
20.39 867
21.39 868
22.39 869
23.39 870
24.39 871
25.39 872
26.39 873
27.39 874
28.39 875
29.39 876
30.39 877
31.39 878
1.40 879
2.40 880
3.40 881
4.40 882
5.40 883
6.40 884
7.40 885
8.40 886
9.40 887
10.40 888
11.40 889
12.40 890
13.40 891
14.40 892
15.40 893
16.40 894
17.40 895
18.40 896
19.40 897
20.40 898
21.40 899
22.40 900
23.40 901
24.40 902
25.40 903
26.40 904
27.40 905
28.40 906
29.40 907
30.40 908
31.40 909
1.41 910
2.41 911
3.41 912
4.41 913
5.41 914
6.41 915
7.41 916
8.41 917
9.41 918
10.41 919
11.41 920
12.41 921
13.41 922
14.41 923
15.41 924
16.41 925
17.41 926
18.41 927
19.41 928
20.41 929
21.41 930
22.41 931
23.41 932
24.41 933
25.41 934
26.41 935
27.41 936
28.41 937
29.41 938
30.41 939
31.41 940
1.42 941
2.42 942
3.42 943
4.42 944
5.42 945
6.42 946
7.42 947
8.42 948
9.42 949
10.42 950
11.42 951
12.42 952
13.42 953
14.42 954
15.42 955
16.42 956
17.42 957
18.42 958
19.42 959
20.42 960
21.42 961
22.42 962
23.42 963
24.42 964
25.42 965
26.42 966
27.42 967
28.42 968
29.42 969
30.42 970
31.42 971
1.43 972
2.43 973
3.43 974
4.43 975
5.43 976
6.43 977
7.43 978
8.43 979
9.43 980
10.43 981
11.43 982
12.43 983
13.43 984
14.43 985
15.43 986
16.43 987
17.43 988
18.43 989
19.43 990
20.43 991
21.43 992
22.43 993
23.43 994
24.43 995
25.43 996
26.43 997
27.43 998
28.43 999
29.43 1000
30.43 1001
31.43 1002
1.44 1003
2.44 1004
3.44 1005
4.44 1006
5.44 1007
6.44 1008
7.44 1009
8.44 1010
9.44 1011
10.44 1012
11.44 1013
12.44 1014
13.44 1015
14.44 1016
15.44 1017
16.44 1018
17.44 1019
18.44 1020
19.44 1021
20.44 1022
21.44 1023
22.44 1024
23.44 1025
24.44 1026
25.44 1027
26.44 1028
27.44 1029
28.44 1030
29.44 1031
30.44 1032
31.44 1033
1.45 1034
2.45 1035
3.45 1036
4.45 1037
5.45 1038
6.45 1039
7.45 1040
8.45 1041
9.45 1042
10.45 1043
11.45 1044
12.45 1045
13.45 1046
14.45 1047
15.45 1048
16.45 1049
17.45 1050
18.45 1051
19.45 1052
20.45 1053
21.45 1054
22.45 1055
23.45 1056
24.45 1057
25.45 1058
26.45 1059
27.45 1060
28.45 1061
29.45 1062
30.45 1063
31.45 1064
1.46 1065
2.46 1066
3.46 1067
4.46 1068
5.46 1069
6.46 1070
7.46 1071
8.46 1072
9.46 1073
10.46 1074
11.46 1075
12.46 1076
13.46 1077
14.46 1078
15.46 1079
16.46 1080
17.46 1081
18.46 1082
19.46 1083
20.46 1084
21.46 1085
22.46 1086
23.46 1087
24.46 1088
25.46 1089
26.46 1090
27.46 1091
28.46 1092
29.46 1093
30.46 1094
31.46 1095
1.47 1096
2.47 1097
3.47 1098
4.47 1099
5.47 1100
6.47 1101
7.47 1102
8.47 1103
9.47 1104
10.47 1105
11.47 1106
12.47 1107
13.47 1108
14.47 1109
15.47 1110
16.47 1111
17.47 1112
18.47 1113
19.47 1114
20.47 1115
21.47 1116
22.47 1117
23.47 1118
24.47 1119
25.47 1120
26.47 1121
27.47 1122
28.47 1123
29.47 1124
30.47 1125
31.47 1126
1.48 1127
2.48 1128
3.48 1129
4.48 1130
5.48 1131
6.48 1132
7.48 1133
8.48 1134
9.48 1135
10.48 1136
11.48 1137
12.48 1138
13.48 1139
14.48 1140
15.48 1141
16.48 1142
17.48 1143
18.48 1144
19.48 1145
20.48 1146
21.48 1147
22.48 1148
23.48 1149
24.48 1150
25.48 1151
26.48 1152
27.48 1153
28.48 1154
29.48 1155
30.48 1156
31.48 1157
1.49 1158
2.49 1159
3.49 1160
4.49 1161
5.49 1162
6.49 1163
7.49 1164
8.49 1165
9.49 11

PLANK FLUJ 5" STATION (CUBIC FEET) SURFACE PER MULTIPLE PLAN-RATIO CALCULIC COMPUTATIONS
 PLUS 10 CUBIC FEET PER SECOND (CUBIC FEET PER SECOND)
 AREA IN SQUARE FEET (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIO	2	3	4	5	6	7	8	9	10
PERIOD	1	7.00	1	2.00	4.00	5.00	6.00	7.00	8.00	9.00	10.00	11.00	12.00
STATION	1	(27.00, 0.00)	(57.00)	(110.00)	(140.00)	(170.00)	(200.00)	(230.00)	(260.00)	(290.00)	(320.00)	(350.00)	(380.00)
	1	(27.00, 0.00)	(57.00)	(110.00)	(140.00)	(170.00)	(200.00)	(230.00)	(260.00)	(290.00)	(320.00)	(350.00)	(380.00)

APPENDIX D
REFERENCES

APPENDIX D


REFERENCES

- 1) U.S. Department of Commerce, Technical Paper No. 40, Rainfall Frequency Atlas of the United States, May 1961.
- 2) Soil Conservation Service, National Engineering Handbook, Section 4, Hydrology, August 1972 (U.S. Department of Agriculture).
- 3) H.W. King and E.F. Brater, Handbook of Hydraulics, 5th edition, McGraw-Hill, 1963.
- 4) T.W. Lambe and R.V. Whitman, Soil Mechanics, John Wiley and Sons, 1965.
- 5) W.D. Thornbury, Principles of Geomorphology, John Wiley and Sons, 1969.
- 6) University of the State of New York, Geology of New York, Education Leaflet 20, Reprinted 1973.
- 7) Cornell University Agriculture Experiment Station (compiled by M.G. Cline and R.L. Marshall), General Soil Map of New York State and Soils of New York Landscapes, Information Bulletin 119, 1977.

APPENDIX E
STABILITY ANALYSIS

46 0782

K&E 10 X 10 TO THE INCH • 7 X 10 INCHES
KLUFFEL & ESSER CO. MADE IN U.S.A.



INPUT FOR STABILITY ANALYSIS PROGRAM

<u>Input Location</u>	<u>Input Parameter Description</u>
0	Unit Weight of Dam (K/ft. ³)
1	Area of Segment #1 (ft. ²)
2	Location of Center of Gravity from toe (ft.) Segment #1
3	Area of Segment #2 (ft. ²)
4	Location of CG from toe, Seg. #2 (ft.)
5	Area of Segment #3 (ft. ²)
6	Location of CG from toe, Sg. #3 (ft.)
7	Total Base Width of Dam (ft.)
8	Height of Dam (ft.)
9	Ice Loading (K/L.F.)
10	Coefficient of Sliding
11	Unit Weight of Soil (K/ft. ³)
12	Coefficient of Active Soil Pressure - Ka
13	Coefficient of Passive Soil Pressure - Kp
14	Height of Water over Top of Dam (ft.)
15	Height of Soil for Active Pressure (ft.)
16	Height of Soil for Passive Pressure (ft.)
17	Height of Water in Tailrace Channel (ft.)
18	Unit Weight of Water (K/ft. ³)
19	Area of Segment #4 (ft. ²)
20	Location of CG from toe, Seg. #4 (ft.)
46	Height of Ice Load or Active Water
49	Location of Foundation Drains from Heel (ft.)
50	Seismic Coefficient (α).

Browns Reservoir Dam

Stability Analysis - Input Parameters

Input Location	Case I	Case II	Case III	Case IV	Case V
00	.15				
01	60				
02	13				
03	20.5				
04	99				
05	16.7				
06	7.6				
07	15				
08	9.8				
09	0	5	0	0	0
10	7				
11	06				
12	249				
13	2.1				
14	0	0	4.3	5.1	0
15	9.8				
16	5.9				
17	0	0	4.3	5.1	0
18	0624				
19	29.4				
20	3.3				
46	9.8				
50	0	0	0	0	0.1

46 0782

K&S 10 X 10 TO THE INCH, 1/2 X 10 INCHES
KEUFFEL & ESSER CO. MADE IN U.S.A.

BROWNS RESERVOIR DAM
STABILITY ANALYSIS
SPILLWAY SECTION

Case I Normal Loading

- (a) 3.195850942
- (b) 8.84157392
- (c) 3.305328359

Case II Ice Loading

- (a) 1.732275324
- (b) 5.439646324
- (c) 1.408737341

Case III 1/2 PMF

- (a) 2.300161525
- (b) 8.49234380
- (c) 1.804041338

Case IV PMF

- (a) 2.191315294
- (b) 8.447680212
- (c) 1.670850056


Case V Seismic Loading

- (a) 2.39459755
- (b) 7.494274656
- (c) 2.064795441


NOTE: (a) is the factor of safety for overturning;
(b) is the location of the resultant from the toe;
(c) is the factor of safety for sliding.

APPENDIX F

DRAWINGS



VICINITY MAP




TOPOGRAPHIC MAP


BROWNS RESERVOIR DAM

LIST OF DRAWINGS

<u>DESCRIPTION</u>	<u>DRAWING NUMBER</u>
GENERAL PLAN	
GATE CHAMBER and PIPE PLAN (1909)	Sheet No 7
GATE CHAMBER and PARAPET WALL DETAIL PLAN (1909)	Sheet No 8
PLAN (1924)	1
SECTIONS (1924)	2
SPILLWAY & GATEHOUSE WALL (1924)	3
SECTIONS (1924)	4



PLANS AND DETAILS
OF PROPOSED WORK AT
BROWN RESERVOIR
FOR THE
FIRST TAXING DISTRICT
OF THE
CITY OF NORWALK, CONN.
FEB. 1924 SCALE 1"




TAILS
AT
VOIR

The Samuel W Hoyt, Co., Inc. Engineers
So. Norwalk, Conn.

STRICT


CONN.


SCALE 1"=50'



BROWN RESERVOIR

Co., Inc. Engineers
nn.





SECTION THRU PRESENT DAM SHOWING CONDITIONS

~ Notice ~

After completing these plans it was decided to substitute common embankment for puddle fill on the down stream side of core wall and to also substitute sand and gravel joints for cement grout in paving work on up stream slope of dam.

SCALE

District
John D
Edward
Wallace

5" paving rammed 3" into fill.
also grouted with 1-3-5 Concrete

Proposed Flow Line Elev 416.5

Present surface
of ground

th Dam.

be set 6 ft apart.
ll, extending 9"

slope 2 to 1

Present Flow Line Elev. 410.5

PLANS AND DETAILS
OF PROPOSED WORK AT

DAM

BROWN RESERVOIR

FOR THE

FIRST TAXING DISTRICT

OF THE


CITY OF NORWALK, CONN.

strict Commissioners
n D. Milne
ward J. Finnegan
lace Dann.

SCALES
as noted


FEB. 1924.

The Samuel W. Hoyt, Jr.,
Engineers.



SECTION THRU STA. 8+25 SCALE 1"=5'

SHOWING NEW DAM



SECTION THRU STA 13+00 Scale 1"=5'

SHOWING NEW DAM.

(FOR OTHER SECTIONS SEE SHEET NO. 4.)

gt. Jr. Co. Inc.

3

Elev 420.0

7'-0"

Elev. 418.5

Earth fill Puddle

5' paving rammed 3" into fill and grouted with 1-3-5 concrete

Slope 2 to 1

Present surface of ground

Proposed Flow Line, Elev 416.5

Estimated Hard Pan foundation

RU STA. 8+25 SCALE 1"=5'

NEW DAM

Elev. 420.0

7'-0"

Earth fill puddle

5' paving rammed 3" into fill and grouted with 1-3-5 concrete

Slope 2 to 1

Present surface of ground


Estimated Hard bottom foundation

RU STA 13+00 Scale 1"=5'


NEW DAM.

SEE SECTIONS SEE SHEET N° 4.)


2




PLAN OF SPILLWAY



SECTION OF AT NORTH WALL



SECTION OF AT SOUTH WALL



PLAN AND DETAILS
OF PROPOSED WORK AT
BROWN RESERVOIR
FOR THE
FIRST TAXING DISTRICT
OF THE
CITY OF NORWALK, CT


FEB 1924

The Samuel W Hoyt


SCALES
as noted

District Commissioners
John D. Milne
Edward J. Finnegan
Wallace Dann

SCALE 1"=20'



New Spillway Elev 416.5
Present Spillway Elev 410.5




SECTION OF WING WALL
THRU ϕ OF DAM SCALE 1"=5'

SCALE 1"=5'

W Hoyt, Jr, Co Inc
Engineers.


414
ters

1-6:



PLAN SHOWING
GATE HOUSE & WALL
(FOR SECTION
SEE SHEET 4) SCALE

Top of Present Dam



Present Dam


RESERVOIR SIDE










PLAN SHOWING
GATE HOUSE & WALL
(FOR SECTION
SEE SHEET 4)

SCALE 1" = 5'

3

4







SECTIONS OF NEW WORK
SCALE 1"=10'

PLAN
OF
BROWN
FIRST T
CITY OF


SCALES
as noted




Sta. 13+00



Sta. 13+25



Sta. 13+50



Sta. 13+75

PLANS AND DETAILS OF PROPOSED WORK AT BROWN RESERVOIR FOR THE FIRST TAXING DISTRICT OF THE CITY OF NORWALK, CONN.

SCALES
as noted


FEB. 1924.

The Samuel W. Hoyt & Co. Inc.
Engineers

District Commissioners
John D. Milne
Edward J. Finnegan
Wallace Donn

SECTIONS OF NEW WORK
SCALE 1"=10'

4



SHEET NO EIGHT

GATE CHAMBER AND PAVEMENT


SCALE ONE INCH = FOUR FEET

C.N. WOOD C.E.

1909

OUTLET PAVEMENT






GATE CHAMBER
PLAN

CHAMBER UP TO 414 ELE WITH THE EXCEPTION THAT THE NORTH OR INSIDE WALL AND THE TWO SIDE WALLS
UMB. UPON THE INSIDE OF THE WELL . MAKING MORE ROOM AT THE TOP .

OUTLET PRESET




10.5
FRONT



AND THE TWO SIDE

UPSTREAM
NORTH




144'

1"

445

4524


210
01



1/4 to 1 - slope


DOWN STREAM
SOUTH

UPSTREAM
NORTH



GATE CHAMBER
ELE.

BROWNS RESERVOIR







GATE CHAMBER ELE.


TH.
BU



4

7











SHEET NO SEVEN
GATE CHAMBER AND PIPE PLAN

SCALE ONE INCH = TEN FEET

C.N. WOOD, C.E.


1909.






30" and 16" pipes upstream from gate chamber to be covered with 6 inches in thickness of concrete
 Space between pipes to be filled to an elevation 6 inches above the 16 inch pipe





30" and 16" pipes upstream from
Space between pipes




SECTION
SCALE 1"

BROWN'S RESERVOIR


3

Sheet No. 1



30" and 16" pipes upstream from gate chamber to be covered with 6 inches in thickness of concrete
 Space between pipes to be filled to an elevation 6 inches above the 16 inch pipe

B



SECTION A-B
 SCALE 1" = 4'

VOIR

4

SCOTT'S RESERVOIR


SECTION 15 20



SECTION 23

SECTION 2

TOWN


LEWISBORO






BROWN'S RESERVOIR

Elevation of Spillway 431.8
Capacity - 290,400,000 Gals
Area - 447 Acres





TOWN OF WILTON

4
Total Acreage 158. 1/10

3